

10500 Cherokee Rd District 4



Why was this project needed?

- Cavitation repair from failing culvert pipes

Scope of work executed

- Installed 60' of 36" HDR pipe, 90' of 48" Class III RCP, headwalls, and paved ditch
- Restored and stabilized creek and side slopes
- Restored roadway

Contractor

PB Chenault

Cost

\$165,554.15

For questions, comments, or concerns specifically about any of these projects, please contact:

Bill Boston
Senior Capital Project Manager
Department of Public Utilities
804-646-8161
William.Boston2@RichmondGov.com

To report a water or drainage issue, or if you have a non-emergency service request, please visit RVA311.com or call 311.